

Orano's Progress and Innovations for US NPP D&D

2023 RadWaste Summit

Sebastien Guillot

Orano Decommissioning Services, LLC

June 8, 2023





orano

Contents


- 1. Introduction and recent D&D experience in the world and the U.S.**
- 2. Drivers to innovation in D&D**
- 3. The Vermont Yankee BWR D&D experience**
- 4. The Crystal River Unit 3 PWR D&D experience and current status**
- 5. Conclusion and highlights of Orano's innovation benefits**

Orano Decommissioning Services

Worldwide presence and U.S. operations






**Vermont Yankee
Completed in 2022**



**Crystal River Unit 3
Completing in 2023**

Orano Decommissioning Services

Main schedule and cost drivers to Reactor D&D



Orano Decommissioning Services

Vermont Yankee BWR – First Accelerated Decommissioning



Project ID

Name: Vermont Yankee

Site: Vernon, Vermont

Reactor type: BWR (620 MW)


Scope of work: RPV – RPV Internals segmentation

Work progress:



- ✓ Project Kick-Off – July 2017
- ✓ Site mobilization – March 2019
- ✓ RVI complete – Aug 2021
- ✓ RV complete – Aug 2022

100%

270,000 hours of safe work without a Lost Time Accident



Reactor Vessel Segmentation



Reactor removal **completed** - On track for Plant Accelerated Decommissioning in **< 10 years**



Orano Decommissioning Services


Vermont Yankee BWR – Waste Synopsis

RV / RVI Components



> 1,000 segments

Waste Classification




GTCC

LLRW
Class B & C

LLRW Class A


Waste Packaging



1 HI-SAFE

7 RWC

17 Custom Boxes
13 x 160-Liners



1st use of the MP197HB!

RV + RVI
Full Segmentation and
Packaging
in 38 Containers




VY Reactor Head Custom Box

Orano Decommissioning Services

Innovating with the 'Optimized Segmentation' solution

- US 9,728,287 and US 9,984,780 patents
- The Reactor Vessel receives segments of the Reactor Vessel Internal Structures from which the GTCC components have been extracted
- The non-GTCC internals components are consolidated and encapsulated within the Reactor Vessel
- The resulting monolith is segmented, and each piece is conditioned in individual packages for off-site transportation and disposal



(12) **United States Patent**
Lessard et al.

(10) Patent No.: US 9,728,287 B2
(45) Date of Patent: Aug. 8, 2017

(54) **PACKAGING FOR DECOMMISSIONED AND
DISMANTLED NUCLEAR REACTORS AND
REACTOR COMPONENTS**

(12) **United States Patent**
Lessard et al.

(10) Patent No.: US 9,984,780 B2
(45) Date of Patent: May 29, 2018

(54) **PACKAGING FOR DECOMMISSIONED AND
DISMANTLED NUCLEAR REACTORS AND
REACTOR COMPONENTS**


Orano Decommissioning Services

The Crystal River 3 Segmentation and Packaging Plan


Head Removal and Packaging



GTCC reactor components packaged in 2 RadWaste Canisters for onsite ISFSI storage



Balance of reactor components repositioned inside the vessel and grouted. Vessel is segmented and packaged in 3 custom shipping containers for off-site disposal



Orano Decommissioning Services

CR3 Reactor D&D progress status – Project start

2020

2021

2022

2023



★ 10/2020 – Contract Closure & Project Kick-Off

Site Modifications & Infrastructure Upgrade

Equipment Hatch Enlarged:

- Facilitate equipment transfer, reactor components, and waste containers in and out of the containment building

Initial hatch configuration before the enlargement cuts



Final Hatch configuration



Before



After

GTCC Waste Storage:

- Added 2 NUHOMS® modules to upgrade the CR3 ISFSI for storage of the reactor GTCC waste



During

Orano Decommissioning Services

CR3 Reactor D&D progress status – Reactor Coolant System

2020

2021


2022

2023

Reactor Coolant System Removal

Removal, Packaging, Transportation and Disposal of:

- 4 Pumps
- 4 Motors
- 1 Pressurizer
- Reactor Coolant Piping
- Ancillary Structures



Reactor Coolant System in the 2 “D-Ring” spaces



Motor



Pumps



RCS piping sections



Pressurizer



Pressurizer packaging



Pumps in shipment



Pumps in disposal

Orano Decommissioning Services


CR3 Reactor D&D progress status – Reactor Head

2020

2021

2022

2023



Reactor Head
Removal

Removal, Packaging, Transportation and Disposal of:

- All Control Rod Drive Mechanisms
- Service Structure
- Reactor Head packaged and ready for shipment



Control Rod Drive Mechanisms
removal and packaging



Reactor Head lifted from the
Reactor Vessel




Reactor Head ready for
packaging



Reactor Head packaged and
transferred out of containment



Service Structure segmented and packaged for shipment



Reactor Head packaged and
ready for shipment

Orano Decommissioning Services

CR3 Reactor D&D progress status – GTCC Removal


2020

2021

2022





2023

GTCC Removal




Reactor Vessel Internals Segmentation:

- Segregation of GTCC portion
- GTCC Packaged in RadWaste Canisters



Orano Decommissioning Services

CR3 Reactor D&D progress status – GTCC Packaging



2020

2021

2022

2023


Packaging, Processing and Transfer to the ISFSI of:

- GTCC portion of the Reactor Vessel Internals,
- CR3 site legacy GTCC waste


GTCC
Packaging



Legacy CR3 site GTCC waste consolidated with the reactor GTCC segments in a RWC Liner



Loaded RWC liner ready for packaging



RWC liner loading in the transfer cask and RWC shell



Transfer cask lifted to the handling station for RWC vacuum drying and welding



RWC undergoing weld closure in the transfer cask handling station



Transfer cask ready to deliver the GTCC RWC to the ISFSI



Transfer cask on transfer trailer conveying a GTCC RWC to the ISFSI for dry storage



Transfer of a GTCC RWC into its assigned NUHOMS dry storage module in the CR3 ISFSI

Orano Decommissioning Services

CR3 progress status – Vessel Removal

2020

2021

2022


2023

Reactor Vessel Removal


Reactor Vessel Removal:

1. Internals repackaging inside the Vessel
2. Fuel transfer canal cleanup and drain down
3. Reactor vessel grouting and segmentation
4. Reactor vessel segmentation


1 Non-GTCC internal components were repositioned inside the vessel



3 The vessel grouting and segmentation system is setup on top of the vessel



4 The RV/RVI monolith will be separated from the RCS piping and segmented using Diamond Wire Sawing



2 All RVI underwater activities were completed and the Fuel Transfer Canal was cleaned-up and drained down to prepare for RV dry segmentation work

Orano Decommissioning Services



CR3 progress status – Packaging and shipment for disposal

2020

2021

2022

2023




2

Barge shipment from Florida to Texas



3

Road shipment of the largest “middle” package in Texas




Orano Decommissioning Services

Conclusion – Innovating for more safety and efficiency

Orano has expanded its toolbox and options offered to the industry with access to larger packaging systems and minimized segmentation work

At Crystal River Unit 3, Orano is delivering the first implementation of the Optimized Segmentation **break-through** strategy



Number of LLW Packages / Shipments for the Reactor Components	
Typical BWR / PWR Full Segmentation	~ 50 - 80
Vermont Yankee BWR Full Segmentation	38
CR3 PWR Optimized Segmentation	6



Orano's progress and innovations for US NPP D&D

2023 RadWaste Summit

Sebastien Guillot

Orano Decommissioning Services, LLC

June 8, 2023



orano



orano



@Orano_USA